Abstract Notification dated the 1st June 1940.

The attention of the public is drawn to the notification calling for tenders for restoring Balagar Kempasaruvinakere, Hullatte Village, Tirthahally Taluk, published in pages 1305-1306, Part VI of the *Mysore Gazette*, dated 6th June 1940.

Tenders will be received by the Executive Engineer, Shimoga Division, up to 3 P.M. on 29th June 1940.

Earnest money required for the work is Rs. 60, which should be credited to the Treasury to "17 (a) P.W. Deposits" and challan enclosed.

D. A. HUKERI,
Executive Engineer.

CHITALDRUG DIVISION.

Abstract Notification dated 3rd June 1940.

The attention of the public is invited to the detailed Notification for constructing a bridge across the Vedavathy River near Byadarahally on Hiriyur-Dharampur Road, published in Part VI pages 1357-1359, of the *Mysore Gazette*, dated 6th June 1940.

The last date of the tender is 24th June 1940.

Notification dated 6th June 1940.

1. Sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 2 P.M. on 8th July 1940, for constructing additional blocks to Local Fund Dispensary at Davangere.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Chitaldrug Division, should be addressed to the Executive Engineer, Chitaldrug Division, in a sealed cover and superscribed as "Tender for constructing additional blocks to Local Fund Dispensary at Davangere." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a Treasury challan for having deposited Rs. 800 to "17 (a) P. W. Deposits" (Rupees eight hundred) in cash or Government Promissory Notes or Mysore Government Bonds, duly endorsed at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for the due fulfilment of the contract. Such a deposit in cash will not carry any interest. A further sum of 5 per cent will be recovered in bills to make up a total of 10 per cent.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 8th July 1940 at 4 P.M. The final acceptance of the tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental Schedule Contract Form for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay specifications (1931).

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Chitaldrug, on all working days, between 11 A.M. and 5 P.M. and tender notification may be obtained from that officer on payment of four annas.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of May 1941, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 10 per day, which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will however be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

23. Chamundi brand cement alone to be used.

24. All lumpsum items will be measured and paid at the lowest schedule rates.

Note.—(*a*) The contractor should at his own cost:—

(1) Provide rods, stakes, ropes and labour required in setting out the works.

(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.

(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.

(4) Arrange for protecting work during inclement weather.

(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.

(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.

(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.

(8) Provide arrangements for pumping and baling of water from excavations and foundations, wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.

(9) Afford facilities to any other parties employed upon the work by the P. W. D. so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.

(10) The contractor is responsible for all accidents to workmen, etc., on the work, and he must take precaution against all risk of accidents and, if necessary, provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

Abstract estimate for the cost of constructing three additional blocks to the Local Fund Dispensary at Davangere.

Sl. No.	Particulars of work	Quantity	Per	Rate	Cost
	Ear, Nose and Throat Block.			Rs. a. p.	Rs.
1	Earthwork excavation for foundation and filling in basement	89	C.yds.	0 3 0	
2	Lime mortar concrete	605	C.ft.	0 3 0	
3	Size stone in lime mortar for foundation and basement	1,740	,,	0 4 6	
4	Burnt brick in lime mortar for superstructure	2,608	,,	0 4 0	
5	Cement concrete of 1:3:6 for basement slabs and lintels, etc.	249	,,	0 9 0	
6	Burnt stone slabs 6″ thick dressed and fixed for steps in the rear	8	S.ft.	0 6 0	
7	Teakwood doors ⅓ panelled and ⅔ glazed with 1½″ thick shutters and ventilators at top with iron fittings, etc., complete	68	S.ft.	1 8 0	
8	Teakwood doors fully panelled with 1½″ thick shutters and complete with iron fittings, etc., complete	49	,,	1 8 0	
9	Teakwood windows fully glazed with 1¼″ thick shutters with ventilators at top including iron fittings, etc., complete	132	,,	1 12 0	
10	Teakwood glazed ventilators	14	,,	1 0 0	
11	R. S. joists 12″×5″ including hoisting and fixing, etc., complete	10.2	Cwt.	15 0 0	
12	Roofing with R.C.C. wedge shaped joists with brick nogging and 3″ to 4″ thick kappi at top, 2 courses of flat tiles laid in mortar and plastering top and bottom	10.12	Sqr.	55 0 0	
13	Flooring with 1½″ thick, 1:2½:5 cement concrete over a bed of 3″ lime mortar concrete and ½″ thick red cement plaster finish including cutting lines, etc.	8.45	Sqr.	20 0 0	
14	Fine plastering with lime mortar	39.03	,,	3 0 0	
15	White washing	39.03	,,	0 5 0	
16	Teakwood screens in 3″×2′ frame and ¾″ thick panelled, with doors, wood oiling, iron fittings, etc., complete	213.	S.ft.	1 0 0	
17	Plain brick in lime mortar parapet wall 1½′ high and ¾′ thick including plastering, white-washing, etc.	130¼	R.ft.	0 9 0	
18	Red coloured cement plaster 1½″ thick dado in W. C. and bath rooms	1.13	Sqr.	8 0 0	
19	Cement plaster skirting to a height of 10″	151¾	R.ft.	0 1 6	
20	Painting doors and windows with Government Lac Factory green paint two coats	4.73	Sqr.	4 0 0	
21	Band cornice 6″ wide and 1″ projection	98⅛	R.ft.	0 6 0	
22	Providing and fixing zinc rain water downpour pipes	24	,,	0 8 0	
23	R.C.C. chajja	..	S.ft.	..	
	Ophthalmic Block.				
1	Earthwork excavation for foundation and re filling in basement	98	C.yd.	0 3 0	
2	Broken stone jelly in lime mortar	666	C.ft.	0 3 0	
3	Size stone in lime mortar for foundation and basement	1,935	,,	0 4 6	
4	Burnt brick in lime mortar for superstructure	2,932	,,	0 4 0	
5	Cement concrete 1:3:6 for basement slabs and lintels, etc.	280	,,	0 9 0	
6	Burnt stone slabs 6″ thick dressed and fixed in lime mortar for steps	8	S.ft.	0 6 0	
7	T. W. doors ⅓ panelled and ⅔ glazed with 1½″ thick shutters, ventilators at top with iron fittings, etc., complete	68	,,	1 8 0	
8	Do without ventilators	25	,,	1 6 0	
9	T. W. doors with fully panelled shutters without ventilators on top	49	,,	1 8 0	
10	T. W. windows fully glazed with 1¼″ shutters, iron bars, fittings, etc., complete	99	S.ft.	1 12 0	
11	T. W. glazed ventilators	27	,,	1 0 0	

Sl. No.	Particulars of work	Quantity	Per	Rate	Cost
				Rs. a. p.	Rs.
12	Rolled steel joists including hoisting, fixing, etc., complete	13.75	Cwt.	15 0 0	
13	Roofing with R.C.C. wedge shaped joists with brick nogging 3″ to 4″ kappi at top, two courses of flat tiles laid in mortar including top and bottom plastering	11.09	Sqr.	55 0 0	
14	Flooring with 3″ lime concrete, 1½″ thick 1 : 2½ : 5 cement concrete and ½″ thick red cement topping including cutting lines, etc., complete ..	9.40	,,	20 0 0	
15	Plastering with fine lime mortar two coats ..	43.29	,,	3 0 0	
16	White washing two coats	43.29	,,	0 5 0	
17	Teakwood screen in 3″×2″ frame ¾″ thick panelled with doors and iron fittings and 2 coats of wood oiling, etc., complete	277	S.ft.	1 0 0	
18	Parapet wall of burnt brick in mortar 1½′ high and ¾′ thick including plastering white washing, etc	99⅝	R.ft.	0 9 0	
19	Cement plaster dado ½″ thick and 2½′ high in bath and W. C.	1.25	Sqr.	8 0 0	
20	Cement plaster skirting to a height of 10″ .. .	171½	R.ft.	0 1 6	
21	Band cornice	101⅛	,,	0 6 0	
22	Painting doors and windows with Government Lac Factory green paint two coats..	5.16	Sqr.	4 0 0	
23	Providing and fixing zinc rain water down pour pipes	24	R.ft.	0 8 0	
24	R.C.C. chajja	..	S.ft.	..	
	Dental Block.				
1	Earthwork excavation for foundation and filling in basement	89	C.yds.	0 3 0	
2	Lime mortar concrete	605	C.ft.	0 3 0	
3	Size stone in lime mortar for foundation and basement	1,741	,,	0 4 6	
4	Burnt brick in lime mortar for superstructure ..	2,601	,,	0 4 0	
5	Cement concrete 1 : 3 : 6 for basement slabs and lintels, etc.	249	,,	0 9 0	
6	Burnt stone slabs 6″ thick, exposed face dressed for steps	8	S.ft.	0 6 0	
7	T W. doors ⅓ panelled and ⅔ glazed, ventilator at top, with iron fittings, etc., complete	68	,,	1 8 0	
8	Teakwood doors ⅓ panelled and ⅔ glazed without ventilators and with iron fittings, etc., complete ..	25	S.ft.	1 6 0	
9	Do with fully panelled shutters for rear side	25	,,	1 8 0	
10	Teakwood windows fully glazed with 1¼″ hutters, iron bars and iron fittings, etc., complete ..	132	,,	1 12 0	
11	Teakwood glazed ventilators	14	,,	1 0 0	
12	Rolled steel joists including hoisting and fixing ..	10.2	Cwt.	15 0 0	
13	Roofing with trapizoidal joists with brick nogging 3″ to 4″ kappi at top, two courses of flat tiles laid in mortar including top and bottom plastering ..	10.10	Sqr.	55 0 0	
14	Flooring with cement concrete 1 : 2½ : 5, 1½″ thick over 3″ bed of lime concrete with ½″ thick red coloured cement plaster finished including cutting lines, etc., complete	8.45	,,	20 0 0	
15	Plastering with lime mortar	39.02	,,	3 0 0	
16	White washing two coats	39.02	,,	0 5 0	
17	T. W. screen in 3″×2″ frame ¾″ thick with door and wood oiling 2 coats, iron fittings, etc., complete ..	250	S.ft.	1 0 0	
18	Parapet wall of burnt brick in lime mortar 1½′ high and ¾′ thick including plastering, etc.	98⅞	R.ft.	0 9 0	
19	Red coloured cement plaster ½″ thick dado in bath and W. C.	1.10	Sqr.	8 0 0	
20	Cement plaster skirting to a height of 10 inches ..	167	R.ft.	0 1 6	
21	Painting doors and windows with Government Lac Factory green paint	4.69	Sqr.	4 0 0	
22	Band cornice	98⅛	R.ft.	0 6 0	
23	Providing and fixing zinc rain water spouts ..	24	,,	0 8 0	
24	R.C.C. chajja	..	S.ft.	..	

Sl. No.	Particulars of work	Quantity	Per	Rate	Cost
				Rs. a. p.	Rs.
	Front Verandah.				
1	Earthwork excavation for foundation	135	C.yd.	0 3 0	
2	Broken stone jelly in lime mortar concrete ..	963	C.ft.	0 3 0	
3	Size stone in lime mortar for foundation and basement	2,627	C.ft.	0 4 6	
4	R.C.C. columns 1′ square 8′ high including plastering, cap and base as per design anchoring at bottom, etc., complete	46	Each	15 0 0	
5	R. S. joists including hoisting and fixing, etc., complete	44.3	Cwt.	15 0 0	
6	R.C.C. slab over joists	76	C.ft.	0 9 0	
7	Brick in mortar entablature wall above joist ..	1,278	,,	0 4 0	
8	Cement concrete 1 : 3 : 6 for basement slabs ..	197	,,	0 9 0	
9	Roofing with trapezoidal joists with brick nogging, 3″ kappi at top, two courses of flat tiles laid in mortar with plastering top and bottom, etc., complete	15.87	Sqr.	55 0 0	
10	Flooring with 3″ lime concrete 1½″ thick 1 : 2½ : 5 cement concrete and ½″ thick red cement topping including cutting lines, etc., complete ..	11.67	,,	20 0 0	
11	Parapet wall of burnt brick in mortar 1½′ height, 9″ thick including plastering complete ..	262	S.ft.	0 9 0	
12	B. S. slabs 6″ thick exposed face 2 lines dressed and fixing in mortar	145	C.ft.	0 6 0	
13	Cement pointing to basement	3.91	Sqr.	4 0 0	
14	Band cornice	262¾	R.ft.	0 6 0	
15	Providing and fixing rain water spouts	..	,,	0 8 0	
16	R.C.C. chajja	..	S.ft.	..	

B. TIRUMALACHAR,
Executive Engineer.

MEDICAL DEPARTMENT.

MINTO OPHTHALMIC HOSPITAL, BANGALORE.

Abstract Notification dated 23rd May 1940.

The attention of the public is invited to the detailed Tender Notice, dated 20th May 1940, calling for tenders for the supply of furniture to the Minto Ophthalmic Hospital, Bangalore. For details please see pages 1232-1233, Part VI of the *Mysore Gazette*, dated 30th May 1940.

B. N. SITARAMIAH,
Secretary.

CIVIL HOSPITAL, KOLAR GOLD FIELDS.

Abstract Notification dated 28th May 1940.

The attention of the public is invited to the detailed notification, calling for tenders for the supply of Diet articles, etc., required for the Civil Hospital, Branch Dispensary, Maternity and E.D. Hospitals, Kolar Gold Field, from 1st July 1940 to 31st December 1940, published in pages 1311-1315 of Part VI of the *Mysore Gazette*, dated 6th June 1940.

Abstract Notification dated 28th May 1940.

The attention of the public is invited to the detailed Notification, calling for tenders for the supply of Milk required for the Civil Hospital, Branch Dispensary, Maternity and E.D. Hospitals, Kolar Gold Field, from 1st July 1940 to 31st December 1940, published in pages 1315-1316 of Part VI of the *Mysore Gazette*, dated 6th June 1940.

B. K. NARAYANA RAO,
Senior Surgeon.